

**INSTITUTO DE CIENCIAS DE
LA CONSTRUCCIÓN
EDUARDO TORROJA**



C/ Serrano Galvache nº 4
28033 Madrid

Tel.: (34) 91 302 04 40

Fax: (34) 91 302 07 00

director.ietcc.@csic.es

www.ietcc.csic.es



MIEMBRO DE LA EOTA
EOTA MEMBER

EUROPEAN TECHNICAL APPROVAL

ETA – 08/0212

(English language translation, the original version is in Spanish language)

Nombre comercial:

Trade name:

MEPIM

Beneficiario del DITE

Holder of approval:

POLIURETANOS AISMAR S.A

Polig. Ind. avenida del castellar sn ri
Ribaforada 31550 (Navarra). Spain

Área genérica y uso del producto de construcción :

Generic type and use of construction product:

Sistema de Impermeabilización de Cubiertas Aplicado en forma Líquida, basado en Poliuretanos

Liquid Applied Roof Waterproofing Kit, based on Polyurethane

**Validez de :
hasta :**

Validity from / to:

2008 June 06

2009 November 02

El presente Documento de Idoneidad Técnica Europeo contiene:

This European Technical Approval contains:

10 páginas, incluyendo 1 anexo, el cual forma parte del documento

10 pages including 1 annex which form an integral part of the document



Organización Europea para la Idoneidad Técnica
European Organisation for Technical Approvals

I. LEGAL BASES AND GENERAL CONDITIONS

1. This European Technical Approval is issued by the **Instituto de Ciencias de la Construcción Eduardo Torroja** in accordance with:
 - Council Directive (89/106/EEC)¹ of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products, modified by the Council Directive 93/68/EEC of July 1993².
 - *Real Decreto 1630/1992 de 29 de diciembre, por el que se dictan disposiciones para la libre circulación de productos de construcción en aplicación de la Directiva 89/106/CEE³. REAL DECRETO 1328/1995, de 28 de julio, por el que se modifican, en aplicación de la Directiva 93/68/CEE las disposiciones para la libre circulación, aprobadas por el Real Decreto 1630/1992, de 29 de diciembre. (B.O.E. 19.895) y la Orden CTE/2276/2002 de 4 de septiembre.*
 - Common Procedural Rules for Requesting, Preparing and the Granting of European Technical Approvals set out in the Annex of Commission Decision 94/23/EC⁴.
 - Guideline for European Technical Approval of Liquid applied roof waterproofing kits, ETAG 005, edition 2000, Part 1 "General" and Part 6 "Specific stipulations for kits based on polyurethane".
2. The **Instituto de Ciencias de la Construcción Eduardo Torroja** is authorised to check whether the provisions of this European Technical Approval are met. Checking may take place in the manufacturing plant(s) (e.g. concerning the fulfilment of assumptions made in this European Technical Approval with regard to manufacturing). Nevertheless, the responsibility for the conformity of the products to the European Technical Approval and for their fitness for intended use remains with the holder of the European Technical Approval.
3. This European Technical Approval is not to be transferred to other manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those / indicated on page 1/ laid down in the context of this European Technical Approval .
4. This European Technical Approval may be withdrawn by the **Instituto de Ciencias de la Construcción Eduardo Torroja** pursuant to Article 5.1 of the Council Directive 89/106/EEC.
5. Reproduction of this European Technical Approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of the **Instituto de Ciencias de la Construcción Eduardo Torroja**. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European Technical Approval.
6. The European Technical Approval is issued by the Approval Body in its official language. This version corresponds to the version circulated within EOTA. Translations into other languages have to be designated as such.

¹ Official Journal of the European Communities n° L 40, 11.2.1989, p.12

² Official Journal of the European Communities n° L 220, 30.8.1993, p.1

³ Boletín Oficial del Estado n° 34 de 9 de febrero de 01993.

⁴ Official Journal of the European Communities n° L 17, 20.1.1994, p.34

II SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

1 Definition of product and intended use

1.1 Definition of product

The liquid applied roof waterproofing kit, based on polyurethane “MEPIM”, manufactured by the company POLIURETANOS AISAMAR, S.A., consists of a polyurethane resins, mono-component, elastomeric without internal protection layer; which once polymerised conforms an elastic lining, in form of a layer completely bonded to the support (concrete, mortar, ceramic).

The kit contents an internal layer (geo-textile) as enforcement of the membrane.

The minimum layer thickness of the assembled system has to be 1,4 mm and the quantity consumed larger than 1.5 kg/m².

The annex 1 shows the components and the system build-up of the system.

1.2 Intended use

The intended use of this System is the waterproofing of roof against the water, as in liquid as vapour form. This LARWK fulfils the Essential Requirements n° 2 (Safety in case of fire), n° 3 (Hygiene, health and the environment) and n° 4 (Safety in use) of the Construction products directive 89/106/EEC.

The performance levels of this System according to the Guide ETAG 005⁵ Part. 1 and Part. 6 are included in the annex 1.

The provisions made in this European Technical Approval (ETA) are based on an assumed intended working life of the system of 10 years (W2).

The indication given on the working life cannot be interpreted as a guarantee given by the manufacturer, but are only to be regarded as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

2 Characteristics of product and methods of verification

The assessment of the fitness of the liquid waterproofing kit MEPIM for the intended use regard to the Essential Requirements n° 2, 3 and 4 was performed in compliance with the “Guideline for European Technical Approval of liquid applied roof waterproofing kits”, ETAG 005, edition 2000, Part 1: General and Part 6: Specific stipulations for kits based on polyurethane.

2.1 Characteristics of System “MEPIM”

2.1.1 ER. 2 Safety in case of fire

External fire performance

Classification: B_{roof}(t1) according to prEN 13501-5 for supports included in point 1.1.

Reaction to fire

Euroclass F

⁵ ETAG N° 5, "Liquid applied roof waterproofing kits", Official Journal of the European Communities N° C 212/02, 06.09.2002.

2.1.2 ER. 3 Hygiene, health and environment

Resistance to water vapour
(EN 1931)⁶. $\mu < 2.000$

Watertightness
(EOTA TR-003). Watertight

Statement of dangerous substances

According to the manufacture's declaration taking account of the EU database, the product installed does not contain and release any dangerous substance.

Resistance to wind loads
(EOTA TR-4). Pass (>50 KPa)

Resistance to dynamic indentation
(EOTA TR- 6). I₃

Resistance to static indentation
(EOTA TR-7). L₄

Resistance to fatigue movement
(EOTA TR-8). Pass

Resistance to low temperatures effects
(-20°C). Dynamic indentation I₃

Resistance to high temperatures effects (90°C). Static indentation L₁

Resistance to heat ageing (EOTA TR-11)

The samples are exposed to 80°C during 100 days.

Fatigue movement	pass
Dynamic indentation (-20°C)	I ₃
Tensile strength (MPa) (EN-ISO 527-3) (unreinforced)	3,6
Tensile elongation (%) (EN-ISO 527-3) (unreinforced)	170

Resistance to UV-radiation in the presence of moisture (EOTA TR- 10)

The samples are exposed 2000 hours to UV-radiation.

Tensile strength (MPa) (EN-ISO 527-3) (unreinforced)	5,3
Tensile elongation (%) (EN-ISO 527-3) (unreinforced)	670
Dynamic indentation (-10°C)	I ₃

⁶ Resistance to water vapour is lower than 10 MNs/g. NBE CT-79 establishes that a constructive element presents a barrier of vapour when the vapour resistance is bigger than 10 MNs/g.

Resistance to hot water ageing (EOTA TR-12)

The samples are kept in touch with water at 60 °C over 30 days.

Delamination strength (kPa) (Concrete)	2577
Static indentation (90°C)	L ₁

Resistance to plant roots (EN 13948). NPD

2.1.3 ER. 4 Safety in use

Slipperiness. NPD

2.1.4 Related aspects of serviceability

Effect of weather conditions

The system does show changes in its tensile properties, when the system is assembled and cured under two temperature conditions of 0°C and 40°C, but these values obtained complied with the manufacturer's specifications (pass).

Effect of day joints

The delamination strength test performed on a layer assembled over other one, it shows a good delamination strength, being upper to required value of 50 KPa. (pass).

2.2 Identification of components

The characteristics of the components of this System show the following values, which compliance with their respective tolerances stated in the Manufacture Technical Dossier (MTD).

a.- Waterproofing liquid constituted by poliol and isocyanates, with loads and pigments mineral, and additives (anti-air entering, biocides, etc.). The main characteristics of this waterproof liquid are:

Density (g/cm ³) (ISO 1675)	1,25
Dry extract (105°C) (% weight) (EN 1768)	92
Ash content (450°C) (% weight) (EN 1879)	41
Viscosity (cps) (EN-UNE ISO 2555)	5.000

b.- Internal layer by geotextil, used as reinforcement in the specific details

Mass per unit area (g/m ²) (EN 29073-1)	100
Tensile elongation (%) (EN 10319)	40 (L) 50 (T)
Tensile strength (N/5cm) (EN 10319)	4 (L) 5 (T)

According to manufacture's declaration, the components without polymerised of the system MEPIM contain dangerous substances defined in the EU database (Security card, according to national disposition, placed at IETcc).

This ETA is issued for the kit "MEPIM" on the basis of the product composition deposited at IETcc. Changes to the components of the kit or in the production process of the components, which could result in the production process and/or the properties of the product deposited being incorrect should be notified to IETcc before the changes are introduced. IETcc will decide whether or not such changes affect the ETA and consequently the validity of the CE marking on the basis of the ETA and if further assessment/alterations to the ETA shall be necessary.

This approval may be extended with other requirements applicable to dangerous substances resulting from transposed European legislation or applicable national regulations and administrative provisions.

Besides, this approval may be extended with other requirements applicable to the products resulting from other applicable national regulations and administrative provisions.

These requirements need also to be complied with.

3 Evaluation of Conformity and CE marking

3.1 Attestation of Conformity System

The European Commission according to her decision (98/599/EC of October 1998, Official Journal of the European Communities N° L 287, 24.10.1998) on the procedure of attestation of conformity has laid down for this type of material

System 3

for the procedure of attestation of conformity (Annex III, clause 2(ii) second possibility of Directive 89/106/EEC) for liquid applied roof waterproofing kits.

The system 3 provides:

- a) *Tasks for the manufacturer:*
Factory production control.

- b) *Tasks for the approved body:*
Initial type-testing of the product.

3.2 Responsibilities

3.2.1 Tasks for the manufacturer

3.2.1.1 Factory production control

The manufacturer exercises a permanent internal control of production and assures that the obtained results fulfil the quality level demanded. All the elements, requirements and provisions adopted by the manufacturer are documented in a systematic manner in the form of written policies and procedures. This control production system documentation ensures a common understanding of quality assurance and enables the achievement of the required product characteristics according to the Technical European Approval.

The manufacturer shall only use incoming materials supplied with the relevant inspection documents according to the MTD.

The results of the factory production control shall be recorded and evaluated. The records shall include at least the following information:

- Name of the product and of the initial materials,

- type of inspection or control,
- date of manufacture of the product, batch N° if needed, and date of inspection or control of the product or of the initial materials,
- result of inspections or controls and, as far as applicable, comparison with the requirements,
- signature of the person responsible for the factory production control.

The records shall be kept for at least five years.

Further information concerning test, frequency and tolerance are included in the control plan, which is part of the MTD to this ETA placed at IETcc.

3.2.2 Tasks for the Approved Body

3.2.2.1 Initial type-testing of the product

The initial type-testing have been conducted by the IETcc to issued this ETA in accordance with chapter 5 of the guideline “Liquid applied roof waterproofing kits” (ETAG 005) part 1 and 6.

The IETcc has assessed the results of these tests in accordance with chapter 6 of this ETA –Guideline, as part of the ETA issuing procedure.

3.3 CE marking

The CE marking⁷ shall be affixed on the pot of the kit of the roof waterproofing "MEPIM".

In addition to the symbol "CE" the following information shall be given:

- name or identifying mark of the manufacturer and of the factory,
- short definition of the levels of performance (ETAG 005-8), according to annex 1,
- the last two digits of the year in which the CE marking was affixed,
- number of the European technical approval,
- statement on dangerous substances: *the product will be marked according to the national dispositions*,
- reaction to fire: F,
- external fire performance: Broof(t1),
- slipperiness: NPD,
- resistance to plant roots: NPD.

4 Assumptions under which the fitness for use of the product for the intended use was favorably assessed

4.1 Manufacture

Further information about the manufacturing of the kit is laid down in the MTD placed at IETcc.

4.2 Design

The fitness of the respective use for the levels of performance of this System stated in Annex 1 complies with the Spanish national requirements.

⁷ Notes on the CE marking are stated in Guidance Paper D "CE marking under the Construction Products Directive", Brussels 01 August 2002.

In the MTD the manufacture gives information on the quantities consumed and the processing, which shall lead to a thickness of the roof waterproofing of at least 1.4 mm.

4.3 Installation

The fitness of use of this kit can only be assumed if this is installed according to the manufacturer's instructions, which are part of the MTD to this ETA placed at IETcc.

Particularly, it is recommended to consider:

- The kit installation has to be carried out by qualified installers,
- it can only be used the components of the kit indicated in this ETA,
- the supervision of the amount of material used (kg/m^2) and the control visual to check that each coat covers totally the one below, can ensure the minimum thickness of the kits,
- inspection of the roof surface (cleanliness and correct preparation) before applying the roof waterproofing,
- the recommended temperature of the product to be assembled will be between 0°C and 40°C and it will be not admitted support temperatures upper to 45°C . In other conditions it will need to follow the manufacturer's instructions.

Before, the installation of MEPIM, it is recommended to read its security card.

4.4 Manufacturer's responsibilities

It is responsibility of the manufacturer of the product to ensure that the information on all provisions is given to those concerned.

5 Information by the manufacture

5.1 Recommendations on packing, transport and storage

This product is considered inflammable, so it is necessary to follow the security instruction for transport and handle.

The storage must be done at temperatures between 0°C - 45°C , in dry conditions and protected against the sun radiation.

The product must be used 1 year after manufacturing date. Once the pot is opened, the product must be consumed in a week.

Further installation details are laid down in the MTD placed at IETcc.


5.2 Recommendations on use, maintenance and repair

In those roofs with deteriorated areas of the waterproof layers, they will be repaired removing all the deteriorated layers. Afterwards, the new product will be assembled following the installation instruction and the new coats must overlap, at least 3 cm, to the coat not deteriorated.

Further installation details are laid down in the MTD placed at IETcc.



Instituto de Ciencias de la Construcción Eduardo Torroja
CONSEJO SUPERIOR DE INVESTIGACIONES CIENTÍFICAS
c/ Serrano Galvache nº4. 28033 Madrid. Tel: (34) 91 302 04 40 Fax. (34) 91 302 07 00
www.ietcc.csic.es




On behalf of the Instituto de Ciencias de la Construcción Eduardo Torroja

Madrid, 2008 June 08

EL DIRECTOR DEL INSTITUTO DE CIENCIAS
DE LA CONSTRUCCIÓN EDUARDO TORROJA

Carlos Miravittles Torras

Annex 1. System build-up of the roof waterproofing “MEPIM”



Characteristics of the System “MEPIM”

Minimum thickness	1.4 mm
Water vapour diffusion resistant factor	$\mu \approx 1105$
Resistance to wind loads	> 50 KPa
Resistance to plant roots	NPD
Statement on dangerous substances	Does not contain any
Resistance to slipperiness	NPD

Performance levels according to the intended use

External fire performance	NPD
Fire reaction	F
Expected working life	W2 (10 years)
Climatic zone of use	S (Severe)
User loads	P1 (Low)
Roofs slopes	S1 – S4
Minimum surface temperatures	TL3 (- 20 °C)
Maximum surface temperatures	TH4 (90°C)